



*Innovative Onsite Wastewater Products and Services*

[www.scgenterprises.com](http://www.scgenterprises.com)

*Alternative  
Wastewater  
Systems*

*Product  
Distribution*

*Product  
Support*

*Installation  
Assistance*

*Onsite  
Management  
Services*

*Maintenance  
Contracts*

*Effluent  
Sampling*

# Arrey Elementary

*Truth or Consequences West, New Mexico*

## Project Summary:

**Installation / Start-up Date:** June 1, 2011

**Description:** Recirculating Sand Filter

**Design Flow:** 2500 gpd

**Project Engineer:** Zia Engineering

**Installer:** HomePro, Inc.



## System Summary:

### **Collection System:**

- Gravity sewer line

### **Treatment System:**

- Two 2,000-gallon septic tank
- Two 2,000-gallon recirculation tanks and 12' by 42' recirculating sand filter
- 1,200-gallon dosing tank
- Duplex control panel

### **Dispersal System:**

- Pressure distributed drainfield

*Dedicated to Improving the Performance of Onsite Wastewater Systems*